

<b>Project Name:</b>	<b>PARNDON WOOD CREMATORIUM</b>
New Build/refurb:	Refurbishment / New Build
Form of contract:	JCT Int 2005
Contract start date:	April 2008
Completion date:	December 2008
Contract value:	£355,000
Client:	Harlow District Council

**Project Description:**

Renewal of flat roof covering, replacement roof lights, installation of a new air management system. Flat to pitch roof conversion, stone render facade, replacement UPVC Windows.



**Construction details:**

Located in Harlow, Essex works began in mid April 2008 to refurbish the Parndon Wood Crematorium.

Insulating and rendering works are being carried out to the Chapel area along side remodelling and installation of windows and hardwood screens in the reception area.

The creation of a new brick reception area will be carried out and will involve demolition of the old timber clad structure. A new air management system will be fitted on the roof along with the installation of new roof coverings on the entire building and new roof lights.

DDA works will be carried out to the building to bring it up to the required standards and a lightning protection system installed on the roof.

Throughout the project close liaison with the Crematorium manager is being carried out so that the crematorium can remain operational. In order to prevent disruption to the crematorium we currently work on designated days which are Saturday through to Tuesday. Our site set up has been placed in the overflow car park surrounded with green debris netting to lessen the impact of the site cabins.

